



Trees						
Abbr	Species	Supply	Size	Girth	Number	
AMARH	Amelanchier arborea 'Robini Hill'	Heavy Standard ; Clear Stem min. 200 ; BR	350-425cm	12-14cm	2	
BETUTJ	Betula utilis jacquemontii	Heavy Standard ; Clear Stem min. 200 ; BR	350-425cm	12-14cm	2	
MAGKO	Magnolia kobus	Heavy Standard ; Clear Stem min. 200 ; BR	350-425cm	12-14cm	18	
					Total	22

PHODA	Phormium 'Dazzler'	25L	100-125cm	Triple Crown	4
PHOJE	Phormium 'Jester'	25L	100-125cm	Triple Crown	10
PHOYEW	Phormium 'Yellow Wave'	25L	100-125cm	Triple Crown	17
PHOFRRER	Phorinia x fraseri 'Red Robin'	70-90L	225-250cm	Standard: 12-14cm gth	20
PRULUSA	Prunus kuskatanica	70-90L	225-250cm	Standard: 12-14cm gth	9
Total :					60

ILECR	<i>Ilex crenata</i>	Sl	30-40cm	Bushy	1323
					Total :1323

	ELABE	Elaeagnus x ebbingei	10L	80-100cm	Bushy	0.4Ctr	117
	ELALMA	Elaeagnus ebbingei 'Limelight'	10L	80-100cm	Bushy	0.4Ctr	126
	GRILI	Griselinia littoralis	10L	80-100cm	Bushy	0.4Ctr	401
	PRULU	Prunus lusitanica	10L	80-100cm	Bushy	0.4Ctr	709
						Total:	1353

BERCAN	<i>Berberis canadensis</i>	10L	30-40cm Bushy	0.7C/r	Yes	79
BRO	<i>Broussonetia sinensis</i>	10L	30-40cm Bushy	0.7C/r	Yes	109
CEATR	<i>Ceanothus 'Thymifolius' repens</i>	10L	30-40cm Bushy	0.7C/r	Yes	217
CHOPJ	<i>Chioselya 'Aetna Pearl'</i>	10L	40-60cm Bushy	0.7C/r	Yes	96
CHOTES	<i>Chioselya temata 'Sundance'</i>	10L	40-60cm Bushy	0.7C/r	Yes	425
EMER	<i>Eunymnus forunei 'Emerald 'N' Gold'</i>	10L	30-40cm Bushy	0.7C/r	Yes	264
EUDOGEE	<i>Eunymnus forunei 'Emerald Galaxy'</i>	10L	30-40cm Bushy	0.7C/r	Yes	187
HEMAR	<i>Hebe 'Marjorie'</i>	10L	40-60cm Bushy	0.7C/r	Yes	44
HEBE	<i>Hebe 'Mrs Winder'</i>	10L	30-40cm Bushy	0.7C/r	Yes	199
HEPBG	<i>Hebe 'Purple Queen'</i>	10L	40-60cm Bushy	0.7C/r	Yes	160
HEBALBE	<i>Hebe obeliscifolia 'Red Edge'</i>	10L	30-40cm Bushy	0.7C/r	Yes	242
HEPBG	<i>Hebe pinnatifida 'Sutherland'</i>	10L	30-40cm Bushy	0.7C/r	Yes	157
HEUTCA	<i>Heuchera micrantha 'Paislee Purple'</i>	10L	Full-Sl	0.7C/r	Yes	46
HYTHI	<i>Hypericum 'Hidcote'</i>	10L	40-60cm Bushy	0.7C/r	Yes	136
LAVANH	<i>Lavandula angustifolia 'Hidcote'</i>	10L	30-40cm Bushy	0.7C/r	Yes	65
LAVANMU	<i>Lavandula angustifolia 'Hidcote'</i>	10L	30-40cm Bushy	0.7C/r	Yes	100
PRUN	<i>Prunus 'Boulevard' 'Orf-Luyken'</i>	10L	30-40cm Bushy	0.7C/r	Yes	78
ROSOF	<i>Rosmarinus officinalis</i>	10L	30-40cm Bushy	0.7C/r	Yes	63
SARHOCU	<i>Sarcococca humilis</i>	10L	30-40cm Bushy	0.7C/r	Yes	57
SKUJUN	<i>Skimmia japonica 'Rubra'</i>	10L	30-40cm Bushy	0.7C/r	Yes	75
VIDA	<i>Viburnum davidii</i>	10L	40-60cm Bushy	0.7C/r	Yes	21

Total: 2705

[illegible]

AUCJACR	<i>Aucuba japonica</i> 'Crototifolia'	10L	60-80cm	Bushy	0.8Ctr	58
CORALE	<i>Cornus alba</i> 'Elegantissima'	3L	60-80cm	Branched	0.8Ctr	3
ELAPUJA	<i>Elaeagnus pungens</i> 'Maculata'	10L	80-100cm	Bushy	0.8Ctr	58
PHOFRRER	<i>Photinia x fraseri</i> 'Red Robin'	10L	80-100cm	Bushy	0.8Ctr	72
Total :191						

	Medallion turf	Rolawn Ltd
---	----------------	------------

All plants shall conform to BS 3936 and be in accordance with the National Plant Specification. Supplying nurseries shall be registered under the HTA Nursery Certification Scheme. All plants shall be packed and transported in accordance with the Code of Practice for Plant Handling as produced by CPSE.

No species, variety, size or position to be amended without the Landscape Architects prior approval.

If the formation level is compacted it should be ripped through before topsoiling. Topsoil depths to be 300mm for shrub beds and 150mm for grass areas.

All landscape proposals must be referred to by the Structural Engineer during foundation design.

All planting has been indicated making every effort to avoid conflict with highway land. Prior to submission it is the client's responsibility to ensure that all landscaping is reviewed by the project manager/highway engineer to ensure there is no conflict with highway land and future adoptions.

Before trees are planted, the Landscape Contractor shall ascertain the location of drains from the site manager, and shall if necessary make minor adjustments to tree positions to ensure that they are planted at least 1.5m from drains. The Contractor should however be planted no closer to houses/garages than is shown on the drawing, and if shown located in shrub beds, the shape of the latter should be adjusted if necessary to accommodate the revised tree position.

If planting conditions are particularly poor e.g. waterlogged/frozen ground or poor soils, the Site Manager must be notified. All works will halt until conditions are considered acceptable.

All planting must be mulched to a depth of 75mm and in accordance with horticultural best practice guidelines ensuring plants are not buried.

All bare root stock shall be root dipped in an approved water-retaining polymer. If planting is required outside the October-March season, bare root trees will be replaced by a containerised equivalent to be approved by the project landscape architect.

Planting in pedestrian visibility splays: Any planting stock specified in pedestrian visibility splays and exceeding 0.6m in height is to be cut down to 0.45m in height at the time of planting. It shall be maintained at a height not exceeding 0.6m in height in perpetuity.

Trees: All tree locations/anecdotes must be taken into consideration by the project Structural Engineer to ensure the foundation design accords with the specifications set out under Chapter 4.2 of the NHERC Standards. It is the Contractor's responsibility to ensure that all underground services have been located and identified in advance of free pit excavation. No tree/species/location/specification will be amended without prior approval from the project Landscape Architect and/or the Client. Root barriers are to be provided as directed by the project engineer. **All trees to be supplied with 2.0m clear stem unless clearly stated otherwise.**

Specimen Shrubs: All specimen shrubs to be planted in accordance with horticultural best practice guidelines. No feature shrub or climbers species, size or location should be altered without prior approval from the Landscape Architect. Planting beds to be mulched with 75mm layer of bark.

Hedgerows: All ornamental hedgerow shrubs to be planted in accordance with horticultural best practice guidelines. No hedgerow shrub species, size or location should be altered without prior approval from the Landscape Architect. Planting beds to be mulched with 75mm layer of bark.

Shrubs & herbaceous (on plot): All ornamental and amenity shrubs to be planted in accordance with horticultural best practice guidelines. No shrub species, size or location should be altered without prior approval from the Landscape Architect. Individual species to be planted in groups of 3-7 within mixed species beds. Planting beds to be mulched with 75mm layer of bark.

Turf & Seeding: All turf and seeding to be completed in line with horticultural best practice. Seed to be applied at the rate (g/m²) advised by manufacturer/supplier.

