

## GENERAL NOTES

All plants supplied shall comply with the National Plant Specification. Supplying nurseries shall be registered under the Horticultural Trade Association (HTA) Nursery Certification Scheme. All plants shall be packed and transported in accordance with the Code of Practice for Plant Handling as produced by CPSE.

Native species shall be British provenance, where available, and certified to confirm origin.

### Good Horticultural Practice

All landscaping work shall adopt good horticultural practices. Compost, mulch and soil conditioners shall be peat-free. The use of pesticides (herbicides, insecticides, fungicides, slug pellets etc) shall be discouraged. Any pesticides used shall be non-residual, i.e. glyphosate.

### Protection of Existing Trees/Hedgerows

Existing trees/hedgerows retained on or overhanging the site shall be protected in accordance with BS 5837: 2012 'Trees in Relation to Design, Demolition and Construction - Recommendations'. Protection measures shall be implemented prior to any preliminary or preparation works on site.

### Nesting Birds

To ensure compliance with the Wildlife & Countryside Act 1981 (as amended), vegetation clearance shall be undertaken outside the bird nesting season, which generally extends between March and September inclusive, dependent on weather. If birds are found to be nesting any works which may affect them shall be stopped until the young have fledged and the nest abandoned naturally.

### GROUND PREPARATION

#### Formation Level

The site shall be brought to formation level using a suitable fine-graded material where possible to avoid large voids but retain free drainage, and de-compacted to a depth of at least 300mm.

#### Subsoil

Provide a minimum depth of subsoil beneath the topsoil layer as specified below. Where there is insufficient depth excavate and dispose of material, loosen the formation and make up with additional subsoil or second quality topsoil. Grade to smooth flowing contours to achieve specified finished levels of topsoil.

Imported subsoil/second quality topsoil shall be supplied in accordance with BS 9001:2013. It shall be free of pests, diseases, visible fragments and roots of aggressive weeds, sticks, straw, turf and significant quantities of foreign matter such as building materials, vegetation, lumps of clay, and the like. Do not use any materials contaminated with rubbish or other materials that are:

- corrosive, explosive, or flammable
- hazardous to human or animal life
- detrimental to healthy plant growth

Prior to the placement of topsoil, and when ground conditions are reasonably dry, the subsoil shall be thoroughly loosened to full depth. Any stones larger than 75mm and other items including bricks, kerbs, lumps of concrete, plaster, timber, plastic, glass, metal and any other building debris brought to the surface shall be removed.

#### Topsoil

Imported topsoil to **BS 3882: 2015** - multi-purpose for general landscaping operations.

Imported topsoil shall be spread in layers not exceeding 150mm depth to achieve the depths as specified below. Finished levels shall be smooth flowing, free of minor hollows and high spots and fairly mearny with paving, kerbs, edgings, manhole covers and existing levels.

Soil handling operations shall be carried out when the soil is reasonably dry and non-plastic (friable) in consistency (at least 5% below the Lower Plastic Limit). Topsoil shall not be unnecessarily compacted by trampling or trafficking of site machinery. Topsoil handling shall be stopped during and after heavy rainfall, and not continued until the soil is again non-plastic in consistency.

#### Depths & Clearances

Provide a minimum depth of subsoil and topsoil as follows:

- Ornamental Shrubs: 400mm topsoil (maximum) over 200mm (minimum) subsoil with a minimum clearance to formation level of 600mm
- Native Hedges: 300mm topsoil (maximum) over 300mm (minimum) subsoil with a minimum clearance to formation level of 600mm
- Tree pits: 400mm topsoil (maximum) over 600mm (minimum) subsoil with a minimum clearance to formation level of 1000mm

#### New Tree Planting Adjacent Services & Structures

All trees and shrubs, whether existing, felled, or proposed, on or adjacent to the site shall be taken into consideration by the applicant's structural engineer when calculating foundation types and depths.

- No tree shall be planted within 6m of centreline of an adoptable sewer
- All trees planted within 3m of a building or heavily loaded structure shall have their roots deflected away by means of a high density deep application root barrier to avoid direct damage from future tree growth.
- All trees within 2m of a masonry boundary wall, or within 3m of any hard paved surface or underground service, shall have their roots deflected away by the installation of a tree root barrier system to avoid direct damage from future tree growth.

#### Root Barrier System

- For protection of building foundations: ReRoot 2000 high density deep application root barrier as supplied by GreenBlueUrban Ltd., or similar
- For protection of pavements only (surround applications): Root Director preformed root protection system as supplied by GreenBlueUrban Ltd., or similar; size dependent on predicted girth (circumference) of mature trunk (to be advised by manufacturer)
- For protection of pavements & underground services/utilities/linear applications: ReRoot ribbed root barrier as supplied by GreenBlueUrban Ltd., or similar; size dependent on predicted girth (circumference) of mature trunk (to be advised by manufacturer)

Installation in full accordance with manufacturer's instructions.

The Landscape Contractor shall be responsible for acquiring 'As-Built' drain and service plans before commencing work on site.

## LANDSCAPE MAINTENANCE

All new planting and hard landscape areas shall be maintained throughout the year as follows:

- Hard Landscape Areas
  - Sweep up leaf fall under trees and windblown in formal and hard landscape areas
  - Sweep all hard landscape areas to remove dust and debris

### Shrubs & Hedgerows

- Weed Control - All planting beds shall be kept weed free by hand weeding or herbicide treatment. Top up mulch twice annually in spring and autumn to maintain original specified depth
- Firming & Pruning - Firm and prune all newly planted shrubs and hedges in accordance with good horticultural practice to promote healthy, bushy growth and to ensure individual plants establish dense cover as rapidly as possible. Any damaged shoots or branches shall be pruned back to healthy wood
- Trim back growth overhanging adjacent footpaths and parking areas
- Shrubs grown for coloured stems (Dogwood): In the second or third year after planting all stems shall be cut down to 50-75mm above ground level, or to 50mm above the coppice stool if cut down previously, and thereafter every other year to maintain a succession of coloured stems. This shall be carried out in early Spring but outside the bird nesting season.
- Native Mixed Species Hedgerows - Once established, trim hedges on a two-year rotation so that no more than one half of the hedge is cut in any one year to ensure there are always flowers for pollinators in spring and berries for birds in winter. Trimming shall be carried out during the dormant season but outside the bird nesting season which generally extends from March to September inclusive. Where possible, cutting shall be delayed until January/February as hedgerow berries provide an important source of food for birds in autumn/winter
- Hornbeam Hedgerows - Once established, trim twice a year to maintain a more managed appearance; once at the end of June, and again in January or February before the buds form taking care not to disturb nesting birds
- Apply an annual application of slow-release fertiliser to planting beds during March/April in accordance with manufacturer's instructions
- Monitor health and control pests and diseases
- Watering - water as required to ensure establishment and survival (see below)

### Specimen Trees

Individual trees planted as specimens shall be inspected annually during the growing season and maintained as follows:

- Firm and straighten to an upright position as required
- Maintain irrigation systems/pipes in good working order. Irrigation pipes shall be checked and repaired as necessary
- All tree stakes and ties are to be checked and adjusted if too loose, too tight, or if chaffing is occurring. Any broken stakes are to be replaced
- Formative pruning to include: removal of epicormic shoots, deadwood, competing secondary leader shoots, and closely spaced, duplicated branches with potentially weak or light forks. All tree works to be carried out in accordance with BS 3998:2010.
- Apply an annual application of slow release fertiliser during March and April at a rate of 50g per tree
- Watering - water as required to ensure establishment and survival (see below)

### Watering

During the first two years after planting a monitored watering regime shall be implemented, commencing from the end of March/early April to the end of October - depending on weather conditions. Apply water when there has been no appreciable rain for 7 days or when there has been drying winds or very high temperatures.

### Replacement of Failed or Defective Plants

Following the initial 12 months defects period any trees or plants which within a period of 5 years from the completion of the development are missing, found dead, or are seriously damaged or diseased shall be replaced in the next planting season.

## GRASSLAND ESTABLISHMENT & MANAGEMENT

- Establishment (first year after sowing)
  - Areas which fail to germinate or establish shall be re-seeded as required
  - How all newly seeded areas regularly throughout the first year of establishment to control annual weeds and help maintain a balance between faster growing grasses and slower developing wildflowers. Cut to a height c. 40-60mm and remove cuttings if dense.
  - Carefully dig out, pull or spot treat any residual perennial weeds such as Ragwort, Thistles and Dock

### Management once established.

- Flowering Verges - Cut to a height of 30-40mm throughout the growing season (March to October inclusive) to maintain a neat tidy appearance. Remove all arisings and reform edges as required. To permit flowering, mowing shall be relaxed from late June. Resume cutting when the sward gets untidy (after 4-8 weeks).
- Meadow Grass - shall be managed to maximise floristic diversity: cut annually after flowering of desirable species in July or August to a height c.50mm. Cuttings shall be left to dry and shed seed for 1-7 days before removal from site. In more open areas along grass verges mow any re-growth through to late autumn/winter, and again in spring if needed, to maintain a more managed appearance. To permit flowering mowing shall be relaxed from June onwards.
- Continue to dig out, pull or spot treat any residual perennial weeds such as Ragwort, Thistles and Dock

## PLANT SCHEDULE

### SPECIMEN TREES

| Ref | Species                        | Girth (cm) | Form                 | Height    | Root Condition | Qty |
|-----|--------------------------------|------------|----------------------|-----------|----------------|-----|
| AcE | Acer campestre 'Elegant'       | 14-16cm    | Extra Heavy Standard | 425-600cm | Rootball       | 3   |
| Bp  | Betula pendula                 | 20-25cm    | Extra Heavy Standard | min 450cm | Rootball       | 2   |
| Cb  | Carpinus betulus               | 20-25cm    | Extra Heavy Standard | min 450cm | Rootball       | 6   |
| PcC | Pyrus calleryana 'Chanticleer' | 14-16cm    | Extra Heavy Standard | 425-600cm | Rootball       | 4   |
| PpA | Prunus padus 'Aberluri'        | 14-16cm    | Extra Heavy Standard | 425-600cm | Rootball       | 4   |
| Sam | Sorbus aria 'Majestica'        | 14-16cm    | Extra Heavy Standard | 425-600cm | Rootball       | 3   |
| Tc  | Tilia cordata                  | 20-25cm    | Extra Heavy Standard | min 450cm | Rootball       | 4   |

### NATIVE MIXED HEDGE

| Hedge                          | A   | B       | C                       |
|--------------------------------|-----|---------|-------------------------|
| Length (m)                     | 41  | 49      | 60                      |
| Species                        | %   | Height  | Root Condition          |
| Acer campestre (Field Maple)   | 10  | 60-80cm | 1+1 bareroot transplant |
| Cornus sanguinea (Dogwood)     | 15  | 60-80cm | 1+1 bareroot transplant |
| Corylus avellana (Hazel)       | 20  | 60-80cm | 1+1 bareroot transplant |
| Crataegus monogyna (Hawthorn)  | 20  | 60-80cm | 1+1 bareroot transplant |
| Ilex aquifolium (Holly)        | 10  | 60-80cm | 3 litre container       |
| Ligustrum vulgare (Privet)     | 10  | 60-80cm | 1+1 bareroot transplant |
| Viburnum opulus (Guelder Rose) | 15  | 60-80cm | 1+1 bareroot transplant |
| Total                          | 205 | 245     | 300                     |

### NATIVE HORNBEAM HEDGE

| Hedge                       | A   | B       |
|-----------------------------|-----|---------|
| Length (m)                  | 52  | 63      |
| Species                     | %   | Height  |
| Carpinus betulus (Hornbeam) | 100 | 60-80cm |
| Total                       | 260 | 320     |

### NATIVE SHRUBS

| Plot                           | 1  | 2       | 3                       | 4   |
|--------------------------------|----|---------|-------------------------|-----|
| Total Area (m2)                | 72 | 128     | 110                     | 137 |
| Species                        | %  | Height  | Root Condition          | Qty |
| Corylus avellana (Hazel)       | 15 | 60-80cm | 1+1 bareroot transplant | 10  |
| Cornus sanguinea (Dogwood)     | 10 | 60-80cm | 1+1 bareroot transplant | 6   |
| Crataegus monogyna (Hawthorn)  | 15 | 60-80cm | 1+1 bareroot transplant | 10  |
| Eunymus europaeus (Spindle)    | 10 | 60-80cm | 1+1 bareroot transplant | 10  |
| Ilex aquifolium (Holly)        | 10 | 60-80cm | 3 litre container       | 6   |
| Ligustrum vulgare (Privet)     | 10 | 60-80cm | 1+1 bareroot transplant | 6   |
| Prunus spinosa (Blackthorn)    | 10 | 60-80cm | 1+1 bareroot transplant | 7   |
| Rosa canina (Dog Rose)         | 5  | 60-80cm | 1+1 bareroot transplant | 3   |
| Viburnum opulus (Guelder Rose) | 10 | 60-80cm | 1+1 bareroot transplant | 7   |
| Total                          | 72 | 128     | 110                     | 137 |

### ORNAMENTAL SHRUBS

| Species                              | Height    | Size               | Density    | Qty |
|--------------------------------------|-----------|--------------------|------------|-----|
| Amelanchier lamarckii                | 120-150cm | 10 litre container | specimen   | 2   |
| Aucuba japonica 'Rozannie'           | 30-40cm   | 3 litre container  | 4cm2       | 97  |
| Berberis x frikartii 'Amstelveen'    | 30-40cm   | 5 litre container  | 4cm2       | 82  |
| Ceanothus 'Pin Cushion'              | 40-60cm   | 3 litre container  | 4cm2       | 100 |
| Choisya x dewitteana 'White Dazzler' | 30-40cm   | 3 litre container  | 4cm2       | 118 |
| Cornus alba 'Sibirica Variegata'     | 60-80cm   | 3 litre container  | 3cm2       | 96  |
| Cornus alba 'Spaethii'               | 60-80cm   | 3 litre container  | 3cm2       | 102 |
| Cotinus coggrygia 'Royal Purple'     | 60-80cm   | 10 litre container | specimen   | 9   |
| Cotoneaster lacteus                  | 40-60cm   | 3 litre container  | 3cm2       | 64  |
| Elaeagnus x ebbingei 'LimeLight'     | 30-40cm   | 3 litre container  | 3cm2       | 98  |
| Escallonia 'Apple Blossom'           | 40-60cm   | 3 litre container  | 3cm2       | 68  |
| Escallonia 'Crimson Spire'           | 40-60cm   | 3 litre container  | 3cm2       | 47  |
| Eunymus japonicus 'Jean Hugues'      | 30-40cm   | 5 litre container  | 45cm apart | 172 |
| Eunymus fortunei 'Emerald Galety'    | 30-40cm   | 5 litre container  | 4cm2       | 56  |
| Hebe allicans                        | 30-40cm   | 5 litre container  | 4cm2       | 53  |
| Hebe 'Blue Gem'                      | 30-40cm   | 5 litre container  | 4cm2       | 69  |
| Hebe 'Marjorie'                      | 30-40cm   | 5 litre container  | 4cm2       | 47  |
| Hebe 'Mrs Winder'                    | 40-60cm   | 5 litre container  | 4cm2       | 139 |
| Hypericum x 'Hidocle'                | 30-40cm   | 3 litre container  | 4cm2       | 96  |
| Lonicera nitida 'Maygreen'           | 30-40cm   | 3 litre container  | 4cm2       | 91  |
| Mahonia x media 'Charity'            | 60-80cm   | 10 litre container | specimen   | 5   |
| Phormium 'Yellow Wave'               | 60-80cm   | 10 litre container | specimen   | 5   |
| Photinia x fraseri 'Red Robin'       | 30-40cm   | 3 litre container  | 3cm2       | 81  |
| Prunus laurocerasus 'Otto Luyken'    | 30-40cm   | 3 litre container  | 4cm2       | 118 |
| Prunus laurocerasus 'Etna'           | 30-40cm   | 3 litre container  | 45cm apart | 47  |
| Sarcococca hookeriana humilis        | 30-40cm   | 5 litre container  | 4cm2       | 88  |
| Senecio 'Sunshine'                   | 30-40cm   | 3 litre container  | 4cm2       | 99  |
| Viburnum x davidii                   | 20-30cm   | 3 litre container  | 4cm2       | 92  |
| Viburnum x tricus 'Eve Price'        | 30-40cm   | 3 litre container  | 3cm2       | 88  |
| Viburnum x bodnantense 'Dawn'        | 60-80cm   | 10 litre container | specimen   | 4   |


## IMPLEMENTATION PROGRAMME

All soft landscape works including preparatory operations shall be carried out when all building works are complete and before the end of the first planting season, subject to the following constraints:

- No planting or preparatory operations shall take place when the ground is frost bound, covered by snow, excessively wet or waterlogged, or in excessively dry or windy conditions
- Container grown plants may be planted at any time during favourable weather and soil conditions. Watering and weed control to be provided as necessary
- Planting of bare-root and rootballed deciduous trees and shrubs, where specified, shall be carried out from late October to late March. All bare root stock, where used, shall be root dipped in mycorrhizal inoculant such as Alginate or similar, applied in accordance with the manufacturer's recommendations
- Seed shall be sown in autumn or spring during calm weather and not when the ground is frost bound or waterlogged

## KEY

### Proposed Landscaping



**Specimen Tree**  
Tree planting in accordance with BS 8545: 2014 'Trees: from nursery to independence in the landscape - Recommendations'.  
*Estimated mature canopy spread indicated thus*  
*Tree pit indicated thus*


Trees shall be planted into prepared pits to the original root collar. Excavated topsoil and subsoil shall be retained for backfilling. Tree pits shall be at least 300mm wider and 75mm deeper than the tree root system/rootball when fully spread, with a minimum size of 1000mm x 1000mm x 750mm deep for heavy standard (1214cm) trees, and 1200mm x 1800mm x 900mm deep for extra heavy standard (2025cm) trees. Where necessary the depth shall be increased to accommodate the depth of the rootball and to obtain the correct planting level. Fork over the bottom of the pit to an additional depth of 200mm, and leave slightly domed to assist drainage, air movement, and root penetration. Care shall be taken to prevent smearing of tree pit sides.

Tree pits shall be backfilled with excavated topsoil and subsoil, where suitable for re-use, to replicate a natural soil profile comprising no more than 300mm depth of topsoil over suitable sandy subsoil, with a 150mm thick layer of river washed gravel or crushed stone laid at the base of the pit to facilitate drainage. Once backfilled, the tree shall be gently shaken at regular intervals to settle the soil closely around the roots. The backfill shall be firm in layers not exceeding 150mm to a finished level equivalent to the nursery soil mark on the tree.

Trees shall be secured in place with an underground guying system such as the Platimat rootball guying system, or equivalent, with underground guys secured to 1200 x 1200mm treated timber 'deadman' anchors

Tree irrigation bags shall be fitted to all trees to ensure they are irrigated sufficiently during their establishment period.


The finished compacted pit shall receive a 75mm deep 8-35mm organic bark mulch layer to prevent weed growth and retain soil moisture. Mulch shall comprise composted wood chips or bark, free of pests, disease, fungus, and weeds. Prior to application clear all grass and weed growth and water tree thoroughly




**Specimen Tree (hard paved areas)**  
Tree planting in accordance with BS 8545: 2014 'Trees: from nursery to independence in the landscape - Recommendations'

### Trees in Hard Paving


- Tree pits shall be planted into larger 5m x 5m tree pits as denoted by the green honeycomb hatching, incorporating a load-bearing geocellular soil structure system in combination with a specialist imported urban tree soil to provide a minimum 15m3 per tree of uncompacted, good quality drainage soil rising below the establishment and long-term health of the trees - see typical tree pit detail
- Tree pits shall be lined with a root barrier to protect adjacent hard surfaces and underground utilities from future tree growth
- Each tree shall be supported with an underground rootball guying system, e.g. Arbortory (or similar) as supplied by Green Blue Urban
- Each tree shall be fitted with a steel tree grille with porous tree pit surface, e.g. Precast Arborsean standard 1200mm square DTS tree grille frame (or similar), as supplied by Green Blue Urban, incorporating single irrigation inlet as below
- A watering inlet shall be fitted to all tree pits, e.g. RoofRain Urban as supplied by Green Blue Urban, or similar. Install in accordance with manufacturer's instructions, size to suit rootball. All trees shall be watered thoroughly after planting.




**Native Shrubs**  
Planting shall be carried out on a 1m staggered grid for quick, dense cover. Shrubs shall be planted in single species groups of 5-7. See plant schedule for species and sizes.



**Native Mixed Species Hedge Planting**  
To be planted in a double staggered row hedging at 400mm between rows and 450mm centres within each row, and maintained at a height of 1m to allow views through. See plant schedule for species and sizes.



**Native Hornbeam Hedge Planting**  
To be planted in a double staggered row hedging at 400mm between rows and 450mm centres within each row, and maintained at a height of 1m to allow views through. See plant schedule for species and sizes.



**Ornamental Shrub Planting**  
Evergreen and deciduous flowering shrubs planted in single-species groups - see plant schedule for species, sizes, and planting density.

After the final placement of topsoil all areas to be planted shall be treated with a non-residual translocated herbicide to clear existing weeds and herbage, and thoroughly cultivated by hand or machinery to a depth of 300mm incorporating ameliorants as specified below. Hand cultivation shall be carried out to achieve the required finish in areas where machine cultivation is not possible (i.e. adjacent kerbs, manholes and footpath junctions, around retained trees etc.). All weeds, roots, and stones larger than 50mm brought to the surface shall be removed off site.


Container grown plants and bare-root transplants at the sizes stated in the plant schedule shall be planted into cultivated beds in accordance with the planting arrangement. At each planting position sufficient soil shall be excavated from the bed to allow 75mm clearance between either the rootball, or the root ends when fully spread, and the sides and bottom of the planting hole. Each plant shall be set in the centre of the pit, showing its best side to the front. Finely broken back-fill material excavated from the pit shall be packed around the roots. The plants shall be gently shaken to allow fine soil to surround the roots. As soil is returned it shall be lightly consolidated and firmly heeled around the root collar.

All bare root stock shall be root dipped in mycorrhizal inoculant such as Alginate, or similar approved, applied in accordance with the manufacturer's recommendations.


All planting areas shall receive a 75mm deep 8-35mm organic bark mulch layer to prevent weed growth and retain soil moisture. Mulch shall comprise composted wood chips or bark, free of pests, disease, fungus, and weeds. Prior to application clear all grass and weed growth and water soil thoroughly.

**Compost & Ameliorants for Shrub Beds & Hedges**  
A peat-free compost (e.g. PAS100: 2011 Landscape Institute WRAP grade (10mm screened) green compost) shall be applied to a minimum depth of 50mm and worked into the soil. For native hedgerow shrubs compost shall be mixed into the planting pit only. Following this a suitable slow-release fertiliser shall be applied and spread at 50g/m2 to all planted areas.

**Note.** All ornamental and native shrubs shall be set back 500mm from the edge of kerbs around perimeter of car parking bays. Areas to be mulched.



**Bare Mulch Areas**  
8-35mm organic bark mulch comprising composted wood chips or bark, free of pests, disease, fungus, and weeds. Laid to a depth of 75mm over weed control membrane



**Flowery Grass Verge**  
To be seeded with slow growing grasses with a selection of wildflowers that respond well to regular short mowing, e.g. Emorgate EM1, or similar



**Meadow Grass**  
To be seeded with a simple, general purpose mix of native wildflowers and grasses suited to a wide range of soil conditions to provide interest for wildlife, e.g. Emorgate EM1, or similar

Areas to be seeded shall be sprayed out with a glyphosate herbicide and cultivated to a depth of 100mm taking care to protect roots of existing trees retained. All weeds, debris, and stones over 25mm in diameter shall be removed off site and the surface raked to smooth flowing contours with a fine lith. Seed shall be sown in two equal sowings in transverse directions at the rates specified. Sow in autumn or spring during calm weather and not when the ground is frost bound or waterlogged.

## PLANNING

|                                              |      |          |
|----------------------------------------------|------|----------|
| P5: Layout updated                           | LK   | 28.10.22 |
| P4: Layout updated                           | LK   | 03.02.22 |
| P3: Layout updated                           | LK   | 27.08.21 |
| P2: Area between car park & Burton Rd seeded | LK   | 10.06.21 |
| P1: First Issue                              | LK   | 09.08.21 |
| Revisions:                                   | Dwn: | Date:    |

|                                                                                                                                                                                                           |                            |                   |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|-------------------|
| Project:                                                                                                                                                                                                  | Drift Road, Castle Gresley |                   |
| Client:                                                                                                                                                                                                   | ALDI Stores Limited        |                   |
| Drawing:                                                                                                                                                                                                  | Detailed Soft Landscaping  |                   |
| Date:                                                                                                                                                                                                     | 28.10.22                   | Drawn: LK         |
| Dwg No:                                                                                                                                                                                                   | MEL-499-001                | Scale: 1:250 @ A0 |
| Revision:                                                                                                                                                                                                 | p5                         |                   |
| MIDDLEMARCH ENVIRONMENTAL                                                                                                                                                                                 |                            |                   |
| Middlemarch Environmental Ltd, Triumph House, Birmingham Road, Alseley, Coventry CV9 9JZ                                                                                                                  |                            |                   |
| Tel: 01676 525880 Fax: 01676 521400                                                                                                                                                                       |                            |                   |
| The copyright of this drawing is vested in Middlemarch Environmental Ltd. Reproduction in any form, either in whole or in part, is forbidden without the prior written permission of the copyright holder |                            |                   |